



# FTTH Home Connection Standards & Online Acceptance Guide (Volume 1)

Document Number :

Controlled Document :

Issue No : 1

Issue Date : 19/06/2019

Issued By : DGM/Access Network Projects

**Guideline for FTTH Home Connection Services Accelerated Expansion of Fiber Access Network** 



Note: All installation standards mentioned should be strictly adhered. However, due to practical surrounding situations or special customer requests provisioning team can adopt minor changes with the written approval of respective Project Engineer of SLT.

#### **DOCUMENT CONTROL SHEET**

Name : A.S.M. Silmi
Designation : Assistant Engineer
Telephone : 0112421883

Fax :

E-mail : silmi@slt.com.lk

#### **Enforcement/ Revision Table**

Issue No. & Date	Revision No. & Date	Revised Page numbers	Prepared / Updated By	Recommended By	Approved By
Issue 1 19/06/2019	Date	numbers	A.S.M.Silmi/AE-ANP	Mr.A.Prashanthan/Eng -ANP	Mr. Chamara Perera /DGM- ANP

**Guideline for FTTH Home Connection Services Accelerated Expansion of Fiber Access Network** 



Note: All installation standards mentioned should be strictly adhered. However, due to practical surrounding situations or special customer requests provisioning team can adopt minor changes with the written approval of respective Project Engineer of SLT.

#### > Instructions

- Summary page including customer T/P no, address, contact no package info & material consumption (new poles, C-hooks, L-hooks & retainers) must be added to the relevant system
- SLT approved online systems are
  - Huawei Integrated Service Delivery Platform(ISDP)
  - o ZTE Engineering Project Management Systems(EPMS)
  - Nokia Access Network Trace Optimization & Management System(ANTOMS)
- Uploaded Images should comprise with geotag and time stamp.
- Customer satisfaction is a key factor for SLT services. So, every work at customer premises should satisfy his/ her requirements. Get necessary approvals if the customer requirements are not fulfilling SLT standards.
- ❖ Manual PAT sheet attached as Annex 1

**Guideline for FTTH Home Connection Services Accelerated Expansion of Fiber Access Network** 



Note: All installation standards mentioned should be strictly adhered. However, due to practical surrounding situations or special customer requests provisioning team can adopt minor changes with the written approval of respective Project Engineer of SLT.

#### Fiber drop wire drawing

- White colored retainers must be used and properly fixed in L-Hooks.
- There shouldn't be fiber drop wire joints between FDP and drop box.
- If the drop wire length exceeds 500m, 15m coil must be kept in every 500.
- Sag of drop wire cannot be exceeded 0.4m for 40 or less pole span, 0.7m for 40-50m pole span.
- Drop wire clearance from foliage must be less than 1m.
- Drop wire bends should comply with G.657A2/ G.652D standard.
- C-Hook must be fixed firmly at a suitable place and drop wire must be covered by flexible conduit/ spiral.
- Permissible fiber drop wire clearance.
  - Along the road: 4.5m
  - o At Road Crossings: 5.0m
  - At Power Crossings: 600V- 60cm, 600V~7000V- 120cm, 7000V~15000V - 200cm





#### For online PAT

- ✓ Drop wire label to show the meter reading & standard being used.
- ✓ Each Pole to pole segment (a segment must accommodate the Starting pole, in between two poles & the end pole).

### Terminating into FDP

- Fiber drop wire must be terminated with FAC connector (SC/UPC).
- Adequate drop wire coil must be kept & properly arranged inside FDP.
- Customer phone no must be written in FDP card with relevant port no.
- Customer phone no must be labelled on drop wire using a tag/sticker within FDP.
- Drop wire must be taken out properly through a rubber bush and guided through the NC pipe/ ring.
- Site must be cleaned well after the installation.





#### For online PAT

- ✓ FDP label & FAC connected drop wire in a single photo.
- ✓ Updated FDP card.
- ✓ Front view of closed FDP (After completion of the works at FDP).


**Guideline for FTTH Home Connection Services Accelerated Expansion of Fiber Access Network** 



Note: All installation standards mentioned should be strictly adhered. However, due to practical surrounding situations or special customer requests provisioning team can adopt minor changes with the written approval of respective Project Engineer of SLT.

#### Erecting new poles

- Construct new poles with struts and stays where ever required.
- Height of the pole must be decided accordance with SLT standards.
- 1/5th of the pole height must be buried.
- Poles must be erected straightly.






#### For online PAT

- ✓ Pole label of all newly erected poles.
- ✓ Full view of the new pole from three different views (to identify slanted pole erection).

#### Rosette box placing

- Fiber rosette must be properly fixed onto the inner wall at appropriate place (where sufficient safety available and easily reachable) at 0.5m height from floor level.
- FAC properly connected to fiber wire within fiber rosette.
- FAC properly connected to adaptor and fiber wire properly arranged within fiber rosette; adequate fiber coil kept within Fiber Rosette.
- SC/UPC must be placed within fiber rosette.
- No splicing to be accommodated inside rosette.





#### For online PAT

- ✓ Photos to show cable arrangement from C-Hook to Rosette.
- ✓ Full view of fiber rosette showing floor level.
- ✓ Lid opened rosette.
- ✓ Power reading.
- ✓ Drop wire meter reading.

**Guideline for FTTH Home Connection Services Accelerated Expansion of Fiber Access Network** 




Note: All installation standards mentioned should be strictly adhered. However, due to practical surrounding situations or special customer requests provisioning team can adopt minor changes with the written approval of respective Project Engineer of SLT.

#### ONT & other equipment installation

- ONT must be placed in a proper location where connectivity for the instruments can be obtained easily and less interference from other Wi-Fi signals; Extra patch cord length must be neatly arranged and protected.
- ONT must be fixed 1m from ground level and in a way where the ports of the ONT headed downwards.
- Installations of TP Instrument and STB done properly and neatly.
- Cat-5E cables properly extended from ONT to the place of STB; CAT-5E cables neatly stapled at 30cm intervals horizontally and 40cm vertically.
- Cat-5E cables properly extended from ONT to the place of PC; CAT-5E cables neatly stapled at 30cm intervals horizontally and 40cm vertically.
- Internal TP wires neatly extended from ONT to the place of TP Rosette and TP Rosette must be fixed properly.
- Site cleaning properly done inside customer premises after completion of all internal installations/ testing.





- ✓ Get the screen shot of the power value while logged in to ONT.
- ✓ ONT with patch code coil arrangement. Photo must be taken from a reasonable distance to show the surroundings.
- ✓ STB with cable arrangement. Photo must be taken from a reasonable distance to show the surroundings.(if installed by Huawei/ ZTE/ Nokia)
- ✓ Telephone instrument with cable arrangement & portable handset. Photo must be taken from a reasonable distance to show the surroundings. (if installed by Huawei/ ZTE/ Nokia)
- ✓ Properly connected TP rosette. (if installed by Huawei/ ZTE/ Nokia)
- ✓ Cat 5/6 & TP cable lengths. (if indoor cabling done by Huawei/ ZTE/ Nokia)
- ✓ Both side of the customer feedback form.



### **FAC Connector Assembly**

- SC/UPC connector must be used.
- Connector /Adapter must be Blue in Color.
- Fiber insertion loss < 0.5dB.
- FAC connector used inside the FDP to terminate the Outdoor drop wire
- FAC connector used inside the Rosette to terminate Indoor drop wire
- Should follow the instruction manual and use proper tools provided by manufacturer.



**Guideline for FTTH Home Connection Services Accelerated Expansion of Fiber Access Network** 



Note: All installation standards mentioned should be strictly adhered. However, due to practical surrounding situations or special customer requests provisioning team can adopt minor changes with the written approval of respective Project Engineer of SLT.

#### Power Testing – Actual (Using Power Meter)

Get the reading (R1) from the proper port at FDP – Set Power Meter to 1490nm Get the reading (R2) from the Rosette - Set Power Meter to 1490nm Different between the readings (R1- R2) will be the Actual power loss

#### Power Loss Calculation - Theoretical

Fiber attenuation loss - 0.27 dB per km for 1490nm

Splicing - 0.1 dB

SC/UPC adapter - 0.3 dB

Field Assembly connector (FAC) - 0.5 dB

Using these values theoretical loss must be calculated and compare with actual power loss

"Theoretical loss must be approximately equals to Actual loss"



**Guideline for FTTH Home Connection Services Accelerated Expansion of Fiber Access Network** 



Note: All installation standards mentioned should be strictly adhered. However, due to practical surrounding situations or special customer requests provisioning team can adopt minor changes with the written approval of respective Project Engineer of SLT.

## ONT Configuration –ZTE F660

- 01) Login as Administration to bind the ONT with network
  - a. Connect to ONT to laptop
  - b. Type 192.168.1.1 in browser
  - c. Enter administrator password→Login
  - d. Network→PON→SN
  - e. 10 digit phone number entered as password
- 02) Login as user Username: user, Password: user IP: 192.168.1.1
  - a. Configure internet using BB Username & Password
    - i. Go to 'quick Setup'
    - ii. Add PPPoE username and password
    - b. Configure Wi-Fi SSID and Password
      - i. Go to 'Next'
      - ii. Enable SSID→Enter SSID (Wi-Fi U/N)
      - iii. Enter pre shared key (Wi-Fi P/W)→save→Detail Setup
    - c. Set the proper Wi-Fi channel to reduce the interference
      - i. WiFi Channel Monitoring using "InSSIDer Home"
      - ii. Network→WLAN→Basic
      - iii. Channel→Select Channel manually→Submit
    - d. Check the ONT power receiving level and make sure > -28dB
      - i. Status Network Interface → PON information


## ONT Configuration –HUAWEI HG8254H

- 01) Login as Administration to bind the ONT with network
  - a. Connect to ONT to laptop
  - b. Type 192.168.1.1 in browser
  - c. Enter administrator password→Login
  - d. System tools → ONT authentication → password (use 10 digit telephone number of the user) and click <Apply>
- 02) Login as user Username: user, Password: user IP: 192.168.1.1
  - a. Quick Setup → Type internet user name and password and click <Next>
  - b. Quick Setup → Configure WiFi SSID and WiFi password and click <Next>
  - c. WiFi Channel Monitoring
    - i. using "InSSIDer Home"
  - d. To change WiFi Channel manually
    - i. Go to: WLAN→WLAN Advance Configuration→Channel Select channel Manually
  - e. Check the ONT power receiving level and make sure > -28dB
    - i. Go to: Status → Optical Information

**Guideline for FTTH Home Connection Services Accelerated Expansion of Fiber Access Network** 



Note: All installation standards mentioned should be strictly adhered. However, due to practical surrounding situations or special customer requests provisioning team can adopt minor changes with the written approval of respective Project Engineer of SLT.



**Guideline for FTTH Home Connection Services Accelerated Expansion of Fiber Access Network** 



Note: All installation standards mentioned should be strictly adhered. However, due to practical surrounding situations or special customer requests provisioning team can adopt minor changes with the written approval of respective Project Engineer of SLT.

tion of FTTH New Connection (Outdoor Category) (V1.5) (To be filled by Developer during installation.)    Cathorner Address:   Cathorner Name:   Cathorner N	Customer Feedba  5/N Description  1 Have you red 2 Do you satisf 3 Does the dev 4 Do youreally 5 Do they wear 6 Do they wear 7 Have you re our red	Stomu stomu	Stome 1 1 1 2 2 2 5 3 3 3 3 3 4 4	Port:  Stomu  1  1  1	Port:	Port:	Port:	Customer Feedba	FDP Port:	i di (code).	EDB (Code):	FTC (Code):	LFA:	OPMC Area:	Province:	25 S	Beyond)	House (ONT and	Cus tomer	Wiringin		House	Customer	16 Fiber F	15 Internal Ir	for Outdoor	13 (Applicable F	Customer		9 External C	8 for S			5 FDP and F		2 2	š	0	S/N Segment C	Developer(Contractor Na	Project No: 142702	Project Name: FTTH Project (Phase-1)
	Does the developer provide you a friendly service?  Do you reallycheer up with our overall service?  Do they wear the company identity card?  Do they wear the Uniform & SLT authorised Badge?  Have you received the letter about the team identity?	eloper provide you a friendly service? cheer up with our overall service? the companyidentity card? the Uniform & SLT authorised Badge?	eloper provide you a friendly service? Cheer up with our overall service? the company identity card?	eloper provide you a friendly service? cheer up with our overall service?	eloper provide you a friendly service?		Do you satisfy with the neatness of wiring?	Description  Have you received a leaflet briefing the information?	Customer Feedback (To be filled by Customer)							te cleaning properly done inside the house after completion o	nternal TP wires neatly extended from ONT to the place of TP Ro	at-SE cables properly extended from ONT to the place of PC, CAT	at-5E cables properly extended from ONT to the place of STB; CA	istallations of TP instrument and STB done properly and neatly	estallation of ONT properly done and extra Patch Cord length n	ac properly connected to Adoptor and fiber wire properly arran	AC properly connected to fiber wire within Fiber Rossette	ber Rosette properly fixed onto the inner wall at the appropria	nternal Wiring neatly done inside house within a protective cas	te cleaning properly done outside the house after completion	berwire properly taken from outside to inside of house overti	cternal Fiber Wires (to and from Drop Box) neatly installed with	ber Drop Box properly mounted onto the outer wall at 1.5m~2.0	Hook properly fixed to the roof/wall and Fiber Drop Wire prope	te cleaning properly done between FDP and Customer Premiss	ber Drop Wire line properly constructed between FDP and Cust	earance from follage- Not less than 1m	ber Drop Wire Clearance- Along the Road: 4.5m. At Road Crossi	uried denth of newly erected notes: 1/5 of note his abt	AC properly connected to Adoptor and Fiber Drop Wire properly	AC properly connected to outdoor Fiber Drop Wire within FDP		heck Item	me/SLT): ЗОРР LANKA (PVT) LTD		ect (Phase-1)
Available):    Developer Confirmation Remarks   Not OK												Other Services	Peo TV Service		BB Service	fabove internal installation	ssette and TP Rossette pro	-5E cables neatly stappied	.T-5E cables neatly stapple	early all all gen all a protection	eatly arranged and protects	ged within Fiber Rossette;		te place (where sufficient	sing/with an appropreate p	of above external install at	ne wall within a proptective	nin a protective casing/with	)m from ground level	erlyhanged by the Hook	es after completion of inst	omer Premisses; White Col	d	ngs: 5.0m. At Power Cross in	ig a Tag/Sticker within FDP	arranged within FDP						0
wallable):    Developer Confirmation Remarks													IP Address:	Internet speed (Wi-I	Internet speed (wire	S	perlyfixed	at 30cm intervals horizo	d at 30cm intervals hori:	č	ons.	Adequate fiber coll kept	Adams to the second book	safety available and ea	rotection/using a self a	ions	e casing/conduit	an appropreate protec			allations	or retainers used: Retai										
wallable):    Developer Confirmation   Remarks								Remarks						Fi):	ed):			ontally and 40cm vertically	zontally and 40cm vertically			within Fiber Rossette	The Property	sily reachable) at 0.5m hei	dhesive fiber wire, accordi		el wile(0.00/02) asea as il	tion on the outer wall			-	iners properly fixed into L-F		000V- 120cm. 7000V~15000V					raily ir ivo (ii aireau)	Telephone No (provide	Customer Address:	Customer Name:
lity																			У					ight from floor level	ing to the customer		idool ilbel wile allo					Hooks		/ - 200cm						ed):		
	Work done standards a		Sign			Signa			Developer	Set Top Box Type	TP Instrument Ty	ONT Type/Serial	Ont. Pwr Level at	Opt.Pwr.Level at	Opt.Pwr Level at																							OK Not C	Developer Confirm			
	according to qualit nd specifications	ionic	aturo	gnati	0	iture	gnati		Certification	/Serial	pe/Ser	No:	ONT(d	Rosset	FDP(dB																							)K	nation Remarks			
	~		Member	Sta ff			Staff Member		SLT C																								+						SLT Co	7		To be fil

**Guideline for FTTH Home Connection Services Accelerated Expansion of Fiber Access Network** 



Note: All installation standards mentioned should be strictly adhered. However, due to practical surrounding situations or special customer requests provisioning team can adopt minor changes with the written approval of respective Project Engineer of SLT.

#### 

